

North Shore Water Reclamation District, Lake County, IL
Air Piping Replacements – Gurnee WRF and Clavey Road WRF
November 9, 2026/10:00 AM

Project Engineer: Mike Jacobson – Phone Number: 815-444-4486
Email: mjacobson@baxterwoodman.com

Engineer's Estimate is not available for this project.

Pre-bid Conference Info:

A recommended pre-bid conference will be held prior to the Bid opening on the 20th day of October 2026, at 10:00 AM at the North Shore Water Reclamation District, 14770 W. Wm. Koepsel Drive, Gurnee, Illinois 60031, to clarify any questions from the potential bidders.

Description of Work:

The work at the Gurnee WRF generally consists of removing existing 30" and 18" odorous air piping above grade and in the tunnels of the Thickener Control Building, abandoning 30" odorous air piping below grade with flowable fill, and installing new above grade 24" and 30" stainless steel air mains and air main supports from (4) thickener tanks to the inlet of the existing odorous air fan. The work at the Clavey Road WRF generally consists of abandoning existing underground 30" air main piping between the main building (Building 20) and Operating Gallery B (Building 150) with flowable fill, and replacing this air main with 30" stainless steel air piping mounted above grade with air main supports. Concrete and landscaping shall be restored at both sites as needed. Contract to include all start up, testing, and balancing of the new air piping.

Information for Bidders:

Complete digital Bidding Documents are available at <http://www.questcdn.com>, and may be downloaded for a nonrefundable \$22.00 fee by inputting QuestCDN project number **10393557** on the website's Project Search page. Contact QuestCDN at 952-233-1632 or info@questcdn.com for assistance in free membership, registration, downloading, and working with the digital Bidding Documents. Paper sets of Bidding Documents will not be made available.